


**Environmental Impact
Assessment -
Final Assessment Report**

May 2000

 土木工程署
Civil Engineering Department

Agreement No CE 41/98

**Tai O Sheltered Boat Anchorage
Environmental and Drainage
Impact Assessment**

prepared by

Scott Wilson (Hong Kong) Limited

**Environmental Impact
Assessment -
Final Assessment Report**

May 2000


for

Civil Engineering Department (CED)

Agreement No CE 41/98

**Tai O Sheltered Boat Anchorage
Environmental and Drainage Impact
Assessment**

CHECKED



YT Wong (Associate)

APPROVED



Ander Chow (Director)

HongKongdesignoffice
accredited by:



ISO9001:1994
CertificationNo.CC213

TABLE OF CONTENTS

	<i>Page</i>
1. INTRODUCTION	1
1.1 BACKGROUND AND HISTORY OF THE PROJECT	1
1.2 STUDY OBJECTIVES.....	1
1.3 REPORT OBJECTIVES AND CONTENT.....	3
2. TAI O DEVELOPMENT AND ANCHORAGE DESIGN/CONSTRUCTION	4
2.1 EXISTING AND PLANNED TAI O DEVELOPMENT.....	4
2.2 DESCRIPTION OF THE TAI O SHELTERED BOAT ANCHORAGE PROJECT.....	4
2.3 BENEFITS OF THE PROJECT AND IMPLICATIONS OF THE "DO-NOTHING" SCENARIO	5
2.4 CONSIDERATION OF ALTERNATIVES	6
2.5 MANGROVE HABITAT CREATION	7
2.6 DREDGING REQUIREMENTS AND DREDGED MATERIAL BALANCE	8
2.7 FACTORS INFLUENCING DREDGING METHODS	9
2.8 POTENTIAL MANGROVE AREA FORMATION METHODS	10
2.9 CONSTRUCTION METHODS FOR OTHER WORKS.....	13
2.10 PROGRAMME AND PLANT REQUIREMENTS	14
2.11 CONCLUSIONS	15
3. CONSTRUCTION NOISE	16
3.1 INTRODUCTION	16
3.2 LEGISLATION AND APPLICABLE STANDARDS.....	16
3.3 NOISE SENSITIVE RECEIVERS.....	19
3.4 BASELINE CONDITIONS.....	20
3.5 POTENTIAL SOURCES OF IMPACT	20
3.6 ASSESSMENT METHODOLOGIES	21
3.7 EVALUATION OF CONSTRUCTION NOISE IMPACTS.....	25
3.8 MITIGATION OPTIONS.....	26
3.9 RECOMMENDED MITIGATION TECHNIQUES	28
3.10 MITIGATED IMPACTS.....	29
3.11 ENVIRONMENTAL MONITORING REQUIREMENTS.....	30
3.12 CONCLUSIONS	30
4. SEDIMENT CONTAMINATION AND DISPOSAL	31
4.1 INTRODUCTION	31
4.2 SEDIMENT DATA REVIEW	31
4.3 SEDIMENT QUALITY INVESTIGATIONS.....	32
4.4 SEDIMENT AND SEDIMENT CONTAMINANT SOURCES.....	35
4.5 SEDIMENT DISPOSAL OPTIONS	37
4.6 SEDIMENT SUITABILITY FOR MANGROVE ESTABLISHMENT.....	39
4.7 CONCLUSIONS	42
5. WATER QUALITY	43
5.1 INTRODUCTION	43
5.2 WATER SENSITIVE RECEIVERS AND BENEFICIAL USES	43
5.3 LEGISLATION AND APPLICABLE STANDARDS.....	44
5.4 DATA REVIEW	49
5.5 SITE INVESTIGATION RESULTS	53

5.6	EXISTING WATER POLLUTION SOURCES TO TAI O BAY.....	57
5.7	MODELLING OF EXISTING TAI O BAY HYDRODYNAMICS AND WATER QUALITY CONDITIONS	62
5.8	POTENTIAL WATER QUALITY IMPACTS DURING THE WORKS PHASE.....	65
5.9	POTENTIAL WATER QUALITY IMPACTS DURING ANCHORAGE OPERATION	72
5.10	MITIGATION REQUIREMENTS – CONSTRUCTION PHASE	83
5.11	MITIGATION REQUIREMENTS - OPERATIONAL PHASE	87
5.12	ENVIRONMENTAL MONITORING REQUIREMENTS.....	90
5.13	ADEQUACY OF SEWERAGE SYSTEM TO ACCEPT WASTES AND REQUIREMENT FOR A PUBLIC TOILET	91
5.14	CONCLUSIONS	92
6.	TERRESTRIAL AND MARINE ECOLOGY	94
6.1	INTRODUCTION	94
6.2	LEGISLATION AND ASSESSMENT CRITERIA	94
6.3	BASELINE CONDITIONS.....	95
6.4	CONSTRUCTION PHASE IMPACTS.....	109
6.5	OPERATIONAL PHASE IMPACTS.....	116
6.6	MITIGATION OF CONSTRUCTION PHASE IMPACTS	119
6.7	MITIGATION OF OPERATION PHASE IMPACTS.....	122
6.8	SUMMARY OF MITIGATION MEASURES	123
6.9	ECOLOGICAL MONITORING AND AUDIT	124
6.10	CONCLUSIONS	125
7.	FISHERIES	126
7.1	INTRODUCTION	126
7.2	LEGISLATION AND APPLICABLE STANDARDS.....	126
7.3	REVIEW OF EXISTING INFORMATION	126
7.4	FISHERIES SURVEYS AT TAI O.....	127
7.5	CONSTRUCTION PHASE IMPACTS.....	130
7.6	OPERATIONAL PHASE IMPACTS.....	134
7.7	MITIGATION OF CONSTRUCTION PHASE IMPACTS	136
7.8	MITIGATION OF OPERATIONAL PHASE IMPACTS	137
7.9	FISHERIES MONITORING	137
7.10	CONCLUSIONS	137
8.	CULTURAL HERITAGE	138
8.1	INTRODUCTION	138
8.2	LEGISLATION AND APPLICABLE STANDARDS.....	138
8.3	STUDY METHODOLOGY	139
8.4	HISTORY OF THE SALT INDUSTRY AND TAI O.....	140
8.5	ARCHAEOLOGICAL POTENTIAL OF THE STUDY AREA.....	145
8.6	FUNG SHUI OF THE STUDY AREA.....	148
8.7	PROJECT IMPACT PREDICTION AND RECOMMENDED MITIGATION MEASURES.....	152
8.8	CONCLUSIONS	154
9.	REQUIREMENTS FOR WASTE COLLECTION DURING SHELTERED BOAT ANCHORAGE OPERATION	155
9.1	INTRODUCTION	155
9.2	REFUSE COLLECTION AND MANAGEMENT	155
9.3	ESTIMATES OF SOLID WASTE GENERATION AT THE SHELTERED BOAT ANCHORAGE.....	157
9.4	REQUIREMENT FOR A NEW REFUSE COLLECTION FACILITY.....	160

9.5	CONTROL OF FLOATING AND LITTORAL REFUSE	161
9.6	OVERVIEW OF DISPOSAL FACILITIES FOR REFUSE GENERATED BY THE SHELTERED BOAT ANCHORAGE AND ASSOCIATED FEATURES.....	163
10.	SUMMARY AND CONCLUSIONS.....	164
10.1	INTRODUCTION	164
10.2	SHELTERED BOAT ANCHORAGE DESIGN AND CONSTRUCTION METHODOLOGY	164
10.3	NOISE ISSUES	164
10.4	SEDIMENT ISSUES	165
10.5	WATER QUALITY ISSUES	165
10.6	TERRESTRIAL AND MARINE ECOLOGY ISSUES.....	166
10.7	FISHERIES ISSUES	166
10.8	CULTURAL HERITAGE ISSUES	167
10.9	WASTE COLLECTION DURING SHELTERED BOAT ANCHORAGE OPERATION	167
10.10	SUMMARY	168
11.	REFERENCES	179

FIGURES

APPENDICES

Appendix 1	-	Construction Noise Impact Assessment Details
Appendix 2	-	Summary of Vibrocore Sediment Quality Data
Appendix 3	-	Details of Water Quality and Sediment Monitoring Programme
Appendix 4	-	Results of Continuous <i>In Situ</i> Water Quality Testing
Appendix 5	-	Ecological Field Surveys
Appendix 6	-	Background Information on Fisheries at Tai O/North Lantau
Appendix 7	-	Fisheries Surveys
Appendix 8	-	Summary of Vibrocores Inspected for Archaeological Remains