

Appendix 3.9 Predicted Construction Noise Levels (Mitigated - Use of Quiet PME and Movable Noise Barriers)

Cumulative Construction Noise Levels

NSR	Predicted Cumulative Construction Noise Levels, dB(A)																								
	2005						2006						2007												
	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
V06	75	72	74	74	74	75	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	72	72	--
V20	66	64	70	70	70	70	70	70	72	72	71	71	71	74	73	72	72	69	69	69	70	66	66	65	

Note:

-- Not Applicable

Bold value indicates the exceedance of noise criteria of 75 dB(A) for residential uses and 65 dB(A) for school during examination period.