
APPENDIX - 7-1

Construction Groundborne Vibration Sources and Ambient Noise Measurements


Vibration Measurement for Construction TBM KCRC DB320 Kwai Tsing Tunnel




KSL Construction ground-borne noise for drilling and breaking operation Site Vibration Measurements - Typical

Plant	Construction Site	Vibration (rms) at the reference Distance 5.5m from source	Vibration (ppv) at Distance 2m from source
Drilling Rig !	Salisbury Road Overrun Tunnel	0.536 mm/s	-
Handheld Breaker	New world centre site	0.279 mm/s	-
Hydraulic Breaker	TST site	0.298 mm/s	-
Pipepile	MTRC TST Modification		19.3 mm/s


^[1] Crest factor of 4 is assumed in accordance with FTA guidance Manual.
[2] In the Project Profile for FMPH project, ppv of 1.5 mm/s at 10m is adopted, the converted ppv at 2m is 16.8 mm/s. This is comparable to ppv of pipepile in this study.




音樂廳座位圖 Concert Hall Seating Plan




大劇院座位圖 Grand Theatre Seating Plan




Proposed measurement locations (A/C ON)




Proposed measurement locations (A/C ON, except recording studio)



音樂廳座位圖 Concert Hall Seating Plan




大劇院座位圖 Grand Theatre Seating Plan



劇場 Studio Theatre 中央舞台 Arena Stage

AMBIENT NOISE MEASUREMENTS IN HK CULTURAL CENTRE & HK SPACE MUSEUM



Project: KSL EIA

Title: Calculation of Conversion Factors from Floor Vibration to Noise Levels

Date: Jan 2004

H, m	DT o				
	RT, s	h	RT	Others	dB(A)
2.5	0.5	-4.0	-3.0	-20	-27
2.2	0.5	-3.4	-3.0	-20	-26
2.2	1	-3.4	0.0	-20	-23
	0.5	-3.4	-3.0	-20	-26
7	1.8	-8.5	2.6	-20	-26
7	1.4	-8.5	1.5	-20	-27
		2.2 0.5 2.2 1 2.2 0.5 7 1.8	2.2 0.5 -3.4 2.2 1 -3.4 2.2 0.5 -3.4 7 1.8 -8.5	2.2 0.5 -3.4 -3.0 2.2 1 -3.4 0.0 2.2 0.5 -3.4 -3.0 7 1.8 -8.5 2.6	2.2 0.5 -3.4 -3.0 -20 2.2 1 -3.4 0.0 -20 2.2 0.5 -3.4 -3.0 -20 7 1.8 -8.5 2.6 -20

Note:

$$L_w = L_v + 10 \log S + 10 \log \sigma - 34$$

$$L_w = L_p + 10 \log(V/RT) - 14$$

(Ref: Eqt 9.65 of "Noise and Vibration Control Engineering", 1992, Edited by Leo Beranek (Ref: Eqt 3.4 of "Woods Practical Guide to Noise Control", 1972, Ian Sharland

Then,

$$L_p = L_v + 10\log S + 10\log \sigma - 34 - 10\log V + 10\log RT + 14$$

assume :
$$\sigma$$
 =1 (worst case)
V = S x h

Hence.

$$L_p - L_v = -10 \log h + 10 \log RT - 20$$

Where

Lw - Sound Power Level

L_v - Vibration level

L_o - SPL

V - Volume

RT - Reverberation time

σ - Raditaion efficiency


h - average height of volumn

$\mathsf{APPENDIX} - 7\text{-}2$

Sample Calculations for Construction Groundborne Noise

APPENDIX - 7-2-1

Sample Construction Groundborne Noise Calculations NSR - HKCC and HKSM



KSL Construction ground-borne noise for drilling and breaking operation Summary of predicted groundborne noise levels

Date: 16 Nov 2003

Zone 1 (FMPHQ)

Zone i (i iiii i i u)					Estimated	
				Max. Predicted	Distance from	
Construction Plant	NSR	Soil Material	Area	Noise Level, dB(A)	Plant to NSR	Ref.
2 nos. Hydraulic Breakers	HKSM	Marine deposit	1/F Recording Studio	<10	140 m	A1
12 1103. Trydraulic Breakers		manno deposit	1/F Space Theatre	<10	140 m	A1
	нксс	Granite	Grand Theatre	11	110 m	A2
	711100	Ora, mo	Concert Hall	16	70 m	A3
			Studio Theatre	24	30 m	A4
4 nos. Rock drills	нксс	Granite	Grand Theatre	19	110 m	B1
14 flus. Nuck dillis	111100	Olaimo	Concert Hall	24	70 m	B2
			Studio Theatre	32	30 m	B3

Note: See attached sample calculations.

Construction Plant	NSR	Soil Material	Area	Max. Predicted Noise Level, dB(A)	Estimated Distance from Plant to NSR	Ref.
2 nos. Hydraulic Breakers		Marine deposit	1/F Recording Studio	<10	140 m	Note [1]
+ 4 nos. Rock drills	11110111	manno deposit	1/F Space Theatre	<10	140 m	Note [1]
+ 4 1105. NOCK drills	HKCC	Granite	Grand Theatre	20	110 m	Note [1]
	TIROO	Oranico	Concert Hall	25	70 m	Note [1]
			Studio Theatre	33	30 m	Note [1]

Note: [1] Noise summation from individual noise levels above due to construction plant in Zone 1.

Zone 2 (Salisbury Road between KPD to Hankow Road)

Construction Plant	NSR	Soil Material	Area	Max. Predicted Noise Level, dB(A)	Estimated Distance from Plant to NSR	Ref.
4 nos. Hydraulic Breakers	HKSM	Marine deposit	1/F Recording Studio	<10	50 m	C1
14 1103: Trydraulio Breakers			1/F Space Theatre	<10	50 m	C1
	нксс	Granite	Grand Theatre	16	95 m	D1
	111100	Graniko	Concert Hall	19	75 m	D2
			Studio Theatre	30	22 m	D3

Note: See attached sample calculations.

Zone 1 + Zone 2

Lone : Lone I					Estimated	
				Max. Predicted	Distance from	
Construction Plant	NSR	Soil Material	Area	Noise Level, dB(A)	Plant to NSR	Ref.
Zone 1 :	HKSM	Marine deposit	1/F Recording Studio	<10	50 m	Note [2]
2 nos. Hydraulic Breakers + 4 nos. Rock drills	,,,,,		1/F Space Theatre	<10	50 m	Note [2]
Zone 2 : 4 nos. Hydraulic Breakers	нксс	Granite	Grand Theatre	21	95 m	Note [2]
1 1103. Trydraulic Breakers			Concert Hall	26	75 m	Note [2]
			Studio Theatre	35	22 m	Note [2]

Note: [2] Noise summation from individual noise levels above due to construction plant in Zone 1 and Zone 2.

KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES Project :

04-Feb-04 Date:

Site: Zone 1 (FMPHQ)

Zone 1 (FMPHU) Hong Kong Space Museum Construction Activities: Excavator mounted breakers NSR:

NSR Distance, R:

Item		16	Octa 31.5	ave Band F 63	requency, 125	Hz 250	500
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
b	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-28	-28	-28	-28	-28	-28
d	Soil Damping Loss [3], Type = "Clay"	-19.6	-38.5	-40.0	-40.0	-40.0	-40.0
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
f	Floor to Floor Attenuation [5]	-2	-2	-2	-2	-2	-2
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	3	3	3	3	3	3
1	Noise Level at NSR, dB [8]	15	-3	-8	-13	-12	-6
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-42	-42	-34	-29	-21	-10
					=	-9	dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Report Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

Project :

KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date:

05-Feb-04

Site:

Zone 1 (FMPHQ)

NSR:

Hong Kong Cultural Centre - Grand Theatre

Construction Activities: Excavator mounted breakers

110 m

NSR Distance, R:

		16	Octave Band Frequency, Hz 16 31.5 63 125 250 50			500	
Item		10	31.0	•			
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
b	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-26	-26	-26	-26	-26	-26
d	Soil Damping Loss [3], Type = "Rock"	-0.1	-0.3	-0.5	-1.0	-2.0	-4.1
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
e'	Coupling Loss from bedrock to piles [*]	-18	-18	-18	-18	-18	-19
f	Floor to Floor Attenuation [5]	-1	-1	-1	-1	-1	-1
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	3	3	3	3	3	3
1	Noise Level at NSR, dB [8]	19	20	16	11	11	14
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-37	-19	-10	-5	2	10
						11	dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[*] Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996 (see attached calculation Ref. F).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h]

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 05-Feb-04

Site:

Zone 1 (FMPHQ) NSR:

Hong Kong Cultural Centre - Concert Hall Construction Activities: Excavator mounted breakers

NSR Distance, R:

16		40		ave Band F			500
ltem		16	31.5	63	125	250	500
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
b	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-22	-22	-22	-22	-22	-22
d	Soil Damping Loss [3], Type = "Rock"	-0.1	-0.2	-0.3	-0.6	-1.3	-2.5
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
e'	Coupling Loss from bedrock to piles [*]	-18	-18	-18	-18	-18	-19
f	Floor to Floor Attenuation [5]	-1	-1	-1	-1	-1	-1
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	3	3	3	3	3	3
1	Noise Level at NSR, dB [8]	23	24	20	15	16	19
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-33	-15	-6	-1	7	16
					_	16 (dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[*] Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996 (see attached calculation Ref. F).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 05-Feb-04

Site: Zone 2 (Salisbury Road between KPD to Hankow Road)

NSR: Hong Kong Cultural Centre - Studio Theatre Construction Activities: Excavator mounted breakers

NSR Distance, R: 30 m

		Octave Band Frequency, Hz			500		
Item		16	31.5	63	125	250	500
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
b	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-15	-15	-15	-15	-15	-15
d	Soil Damping Loss [3], Type = "Rock"	0.0	-0.1	-0.1	-0.2	-0.5	-1.0
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
e'	Coupling Loss from bedrock to piles [*]	-18	-18	-18	-18	-18	-19
f	Floor to Floor Attenuation [5]	-2	-2	-2	-2	-2	-2
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	3	3	3	3	3	3
1	Noise Level at NSR, dB [8]	30	31	27	22	23	27
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-27	-9	1	6	14	24
						24	dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[*] Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996 (see attached calculation Ref. F).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 21-Nov-03

Zone 1 (FMPHQ)

Item	Description	Quantity
1.	Calculated 2 nos. Hydraulic Breakers	= 11 dB(A)
	Noise Level at HKCC Grand Theatre	Extracted from calculation sheet Ref. A2
	when breaking granite at 110m away	
2.	Calculated 1 nos. Hydraulic Breakers	= 11 dB(A) minus 3 dB(A)
	Noise Level at HKCC Grand Theatre	= 8 dB(A)
	when breaking granite at 110m away	
3.	Correction to Rock Drill Noise	= + 20 log (V1 / V2)
***	V1 = Vibration (rms) of Drilling Rig	= + 20 log (0.536 mm/s / 0.298 mm/s)
	V2 = Vibration (rms) of Hydraulic Breaker	= + 5.1 dB
	Ref.	
	See vibration measurement table in Appendix 7-1	
4.	Multiple source correction	= + 10 log (N)
	for 4 Rock Drills	= + 10 log (4)
		= + 6 dB
5.	Predicted Groundborne Noise	= 19 dB(A)
	Adding items [2], [3] and [4]	

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 21-Nov-03

Zone 1 (FMPHQ)

Item	Description	Quantity
1.	Calculated 2 nos. Hydraulic Breakers	= 16 dB(A)
	Noise Level at HKCC Concert Hall	Extracted from calculation sheet Ref. A3
	when breaking granite at 70m away	
2.	Calculated 1 nos. Hydraulic Breakers	= 16 dB(A) minus 3 dB(A)
	Noise Level at HKCC Concert Hall	= 13 dB(A)
	when breaking granite at 70m away	
3.	Correction to Rock Drill Noise	= + 20 log (V1 / V2)
	V1 = Vibration (rms) of Drilling Rig	= + 20 log (0.536 mm/s / 0.298 mm/s)
	V2 = Vibration (rms) of Hydraulic Breaker	= + 5.1 dB
	Ref.	
	See vibration measurement table in Appendix 7-1	
4.	Multiple source correction	= + 10 log (N)
	for 4 Rock Drills	= + 10 log (4)
		= + 6 dB
5.	Predicted Groundborne Noise	= 24 dB(A)
	Adding items [2], [3] and [4]	

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 21-Nov-03

Zone 1 (FMPHQ)

Item	Description	Quantity
1.	Calculated 2 nos. Hydraulic Breakers	= 24 dB(A)
	Noise Level at HKCC Studio Theatrel	Extracted from calculation sheet Ref. A4
	when breaking granite at 30m away	
2.	Calculated 1 nos. Hydraulic Breakers	= 24 dB(A) minus 3 dB(A)
	Noise Level at HKCC Studio Theatrel	= 21 dB(A)
	when breaking granite at 30m away	
3.	Correction to Rock Drill Noise	= + 20 log (V1 / V2)
	V1 = Vibration (rms) of Drilling Rig	= + 20 log (0.536 mm/s / 0.298 mm/s)
	V2 = Vibration (rms) of Hydraulic Breaker	= + 5.1 dB
	Ref.	
	See vibration measurement table in Appendix 7-1	
4.	Multiple source correction	= + 10 log (N)
	for 4 Rock Drills	= + 10 log (4)
		= + 6 dB
5.	Predicted Groundborne Noise	= 32 dB(A)
	Adding items [2], [3] and [4]	

KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES Project :

Date:

04-Feb-04

Site:

Zone 1 (FMPHQ)

NSR:

Hong Kong Space Museum

Construction Activities: Excavator mounted breakers

NSR Distance, R:

			Octa	eve Band F			
Item		16	31.5	63	125	250	500
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
b	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-19	-19	-19	-19	-19	-19
d	Soil Damping Loss [3], Type = "Clay"	-6.5	-12.8	-25.5	-40.0	-40.0	-40.0
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
f	Floor to Floor Attenuation [5]	-2	-2	-2	-2	-2	-2
9	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	6	6	6	6	6	6
1	Noise Level at NSR, dB [8]	40	35	18	-1	0	5
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-17	-5	-8	-17	-9	2
						4	dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Report Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

Ref. D1

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date : 05-Feb-04

Site: Zone 1 (FMPHQ)

Hong Kong Cultural Centre - Grand Theatre Construction Activities: Excavator mounted breakers NSR:

NSR Distance, R: 95 m

lta		16	Octa 31.5	ave Band F 63	requency,	Hz 250	500
Item		10	31.5	03	123	250	300
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
ъ	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-25	-25	-25	-25	-25	-25
d	Soil Damping Loss [3], Type = "Rock"	-0.1	-0.2	-0.4	-0.9	-1.7	-3.5
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
e'	Coupling Loss from bedrock to piles [*]	-18	-18	-18	-18	-18	-19
f	Floor to Floor Attenuation [5]	-1	-1	-1	-1	-1	-1
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	6	6	6	6	6	6
ł	Noise Level at NSR, dB [8]	24	25	21	15	15	18
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-33	-15	-6	-1	7	15
						16	dB(A)

16 dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[*] Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996 (see attached calculation Ref. F).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

Job No.:

Project :

KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date:

05-Feb-04

Site:

Zone 1 (FMPHQ)

NSR:

Hong Kong Cultural Centre - Concert Hall

Construction Activities: Excavator mounted breakers

NSR Distance, R:

75 m

				ave Band F			500
item		16	31.5	63	125	250	500
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
b	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-23	-23	-23	-23	-23	-23
d	Soil Damping Loss [3], Type = "Rock"	-0.1	-0.2	-0.3	-0.7	-1.4	-2.7
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
e'	Coupling Loss from bedrock to piles [*]	-18	-18	-18	-18	-18	-19
f	Floor to Floor Attenuation [5]	-1	-1	-1	-1	-1	-1
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	6	6	6	6	6	6
1	Noise Level at NSR, dB [8]	26	27	23	18	18	21
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-31	-13	-3	2	9	18
						19	dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

[*] Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996 (see attached calculation Ref. F).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 05-Feb-04

Site: Zone 2 (Salisbury Road between KPD to Hankow Road)

NSR: Hong Kong Cultural Centre - Studio Theatre Construction Activities: Excavator mounted breakers

NSR Distance, R: 22 m

			Octa	eve Band F	requency,	Hz		
item		16	31.5	63	125	250	500	
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091	
ь	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102	
С	Distance Correction = -20 log (R/Ro) [2]	-12	-12	-12	-12	-12	-12	
d	Soil Damping Loss [3], Type = "Rock"	0.0	0.0	-0.1	-0.2	-0.3	-0.6	
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14	
e'	Coupling Loss from bedrock to piles [*]	-18	-18	-18	-18	-18	-19	
f	Floor to Floor Attenuation [5]	-2	-2	-2	-2	-2	-2	
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27	
h	Multiple Source Effect [7]	6	6	6	6	6	6	
l	Noise Level at NSR, dB [8]	35	37	33	28	29	33	
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2	
k	A-weighted Noise Level, dB(A)	-21	-3	7	12	20	30	
					=	30	dB(A)	

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[*] Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996 (see attached calculation Ref, F).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

Appendix - Coupling Loss Calculations from Bedrock to Piles

Ref. F

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 05-Feb-04

NSR: Hong Kong Cultural Centre

Statistical Energy Analysis (SEA)

Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996.

 In SEA, the dynamic variable is energy E. Energy attenuation is related to coupling loss factor η₁₂ between two subsystems 1 and 2, and the total loss factor η₂ of subsystem 2:

Coupling Loss in dB = 10 Log[
$$E_2/E_1$$
] = 10 Log [η_{12}/η_2]

2. Coupling loss factor (CLF) from one structure to another is given by Equation (4.32) in the Reference:

$$\eta_{12} = 0.1365 [h_1 c_{11}/f]^{1/2} (L_{12}/S_1) \tau_{12}$$

where h_1 = Bedrock thickness in m;

 c_{L1} = Longitudinal wave speed in rock in m/s;

f = Frequency in Hz;

 L_{12} = Structural joint length of piles to bedrock in m;

S, = Impact surface area in sq.m;

 τ_{12} = Transmission loss coefficient.

3. Approximation to total loss factor of concrete or similar is given by:

$$\eta_2 = f^{-1/2} + 0.015$$

4. Input Parameters:

Remark:

h₁ = 55 m

Based on geological figures near HKCC.

 $c_{L1} = 3500 \text{ m/s}$

Propagation through rock.

L 12 = 3 m

Depth of piles embedded into bedrock.

 $S_1 = 3200 \text{ sq.m}$ $r_{12} = 1/3$ Tunnel width = 2 nos. x 8m = 16m; Tunnel section along HKCC = 200m. Power splitted - assume one part in piles and two parts in bedrock. This is considered as a conservative approximation due to the large difference between

bedrock thickness (>55m) and typical piles size (1~3m in diameter)

5. Coupling Loss Calculations:

								Coupling
f, Hz	h ₁ ,m	c _{L1} , m/s	L 12, m	S ₁ , sq.m	T 12	η 12	η 2	Loss, dB
16	55	3500	3	3200	0.333	0.00468	0.26500	-18
32	55	3500	3	3200	0.333	0.00331	0.19178	-18
63	55	3500	3	3200	0.333	0.00236	0.14099	-18
125	55	3500	3	3200	0.333	0.00167	0.10444	-18
250	55	3500	3	3200	0.333	0.00118	0.07825	-18
500	55	3500	3	3200	0.333	0.00084	0.05972	-19

APPENDIX - 7-2-2

Sample Construction Groundborne Noise Calculations NSR - YMCA

KSL Construction ground-borne noise for drilling and breaking operation Summary of predicted groundborne noise levels

Date: 23 Dec 2003

Zone 1 (FMPHQ)

Lone (1 im 1 loc)					Estimated	
				Max. Predicted	Distance from	
Construction Plant	NSR	Soil Material	Area	Noise Level, dB(A)	Plant to NSR	Ref.
2 nos. Hydraulic Breakers	YMCA	Granite	Guestroom	24	30 m	E1
4 nos. Rock drills	YMCA	Granite	Guestroom	32	30 m	E2

Note: See attached sample calculations.

Construction Plant	NSR	Soil Material	Area	Max. Predicted Noise Level, dB(A)	Estimated Distance from Plant to NSR	
2 nos. Hydraulic Breakers + 4 nos. Rock drills	YMCA	Granite	Guestroom	33	30 m	Note [1]

Note: [1] Noise summation from individual noise levels above due to construction plant in Zone 1.

Zone 2 (Salisbury Road between KPD to Hankow Road)

Zone z (Sansbury Road L	elween r	LPD to Hallkow K	oau)			
					Estimated	
				Max. Predicted	Distance from	
Construction Plant	NSR	Soil Material	Area	Noise Level, dB(A)	Plant to NSR	Ref.
4 nos. Hydraulic Breakers	YMCA	Granite	Guestroom	37	11 m	E3

Note: See attached sample calculations.

Zone 1 + Zone 2

				Max. Predicted	
Construction Plant	NSR	Soil Material	Area	Noise Level, dB(A)	Ref.
Zone 1 :					
2 nos. Hydraulic Breakers					
+ 4 nos. Rock drills					
Zone 2 :					
4 nos. Hydraulic Breakers	YMCA	Granite	Guestroom	38	Note [2]

Note: [2] Noise summation from individual noise levels above due to construction plant in Zone 1 and Zone 2.

KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES Project :

05-Feb-04 Date: Site:

Zone 1 (FMPHQ) YMCA Building Construction Activities: Excavator mounted breakers NSR:

NSR Distance, R:

			Octa	ve Band F	requency,	Hz	
Item		16	31.5	63	125	250	500
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
b	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-15	-15	-15	-15	-15	-15
d	Soil Damping Loss [3], Type = "Rock"	0.0	-0.1	-0.1	-0.2	-0.5	-1.0
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
e'	Coupling Loss from bedrock to piles [*]	-18	-18	-18	-18	-18	-19
f	Floor to Floor Attenuation [5]	-2	-2	-2	-2	-2	-2
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	3	3	3	3	3	3
i	Noise Level at NSR, dB [8]	30	31	27	22	23	27
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-27	-9	1	6	14	24
						24	dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[*] Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996 (see attached calculation Ref. F).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 24-Dec-03

Zone 1 (FMPHQ)

Item	Description	Quantity
1.	Calculated 2 nos. Hydraulic Breakers	= 24 dB(A)
	Noise Level at YMCA Building	Extracted from calculation sheet Ref. E1
	when breaking granite at 30m away	
2.	Calculated 1 nos. Hydraulic Breakers	= 24 dB(A) minus 3 dB(A)
	Noise Level at YMCA Building	= 21 dB(A)
	when breaking granite at 30m away	
3.	Correction to Rock Drill Noise	= + 20 log (V1 / V2)
	V1 = Vibration (rms) of Drilling Rig	= + 20 log (0.536 mm/s / 0.298 mm/s)
	V2 = Vibration (rms) of Hydraulic Breaker	= + 5.1 dB
	Ref.	
	See vibration measurement table in Appendix 7-1	
4.	Multiple source correction	= + 10 log (N)
	for 4 Rock Drills	= + 10 log (4)
		= + 6 dB
5.	Predicted Groundborne Noise	= 32 dB(A)
	Adding items [2], [3] and [4]	

Notes:

[1] Groundborne noise level at other distance is calculated similarly.

Job No.: 23573

KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES Project:

Date: 05-Feb-04

Zone 2 (Salisbury Road between KPD to Hankow Road) Site:

Construction Activities: Excavator mounted breakers YMCA Building NSR:

NSR Distance, R: 11 m

			Octave Band Frequency, Hz				
item		16	31.5	63	125	250	500
а	Source Vibration Velocity, mm/s [1]	0.05886	0.06816	0.06195	0.05033	0.06225	0.12091
b	Vibration Velocity Level, dB ref. 10^-6 mm/s	95	. 97	96	94	96	102
С	Distance Correction = -20 log (R/Ro) [2]	-6	-6	-6	-6	-6	-6
d	Soil Damping Loss [3], Type = "Rock"	0.0	0.0	0.0	-0.1	-0.1	-0.2
е	Building Coupling Loss, BCF [4]	-7	-7	-10	-13	-14	-14
e'	Coupling Loss from bedrock to piles [*]	-18	-18	-18	-18	-18	-19
f	Floor to Floor Attenuation [5]	-2	-2	-2	-2	-2	-2
g	Conversion to Noise [6]	-27	-27	-27	-27	-27	-27
h	Multiple Source Effect [7]	6	6	6	6	6	6
1	Noise Level at NSR, dB [8]	41	43	39	34	35	39
j	A-weighting Correction	-56.7	-39.4	-26.2	-16.1	-8.6	-3.2
k	A-weighted Noise Level, dB(A)	-15	3	13	18	26	36
						37	dB(A)

^[1] Based on site measurement with an excavator-mounted breaker operating at the reference distance Ro = 5.5m.

^[2] Reference: "Transit Noise and Vibration Impact Assessment" issued by the FTA of the U.S. Department of Transport.

^[3] Calculated in accordance with "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-2). Damping loss limited to no greater than 40 dB in any frequency bands.

^[4] Reference: "Transportation Noise Reference Book", 1987 (see EIA Report Table 7-3).

^[*] Reference: "Sound Transmission through Buildings using Statistical Energy Analysis", 1996 (see attached calculation Ref. F).

^[5] Floor to floor attenuation = -1 dB per floor for a conservative assessment.

^[6] Standard acoustic principles (see EIA Table 7-4).

^[7] Breakers in simultaneous operation.

^[8] Octave Noise Level in dB = Items [b] + [c] + [d] + [e] + [f] + [g] + [h].

APPENDIX - 7-2-3

Sample Construction Groundborne Noise Calculations for TBM

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 11-Dec-03 NSR: HKCC

Item	Description	Quantity
1.	Source Term, from Graph	= 2.5 mm/s
	DB320 Kwai Tsing Tunnel by Extrapolation	
	PPV at 5.5m	
2.	Conversion to rms velocity	= 0.625 mm/s
	based on Crest factor of 4	
	Reference: FTA Guidance Manual	
3.	Vibration Velocity	= 20 log (V / Vref)
	ref. 10^-9 m/s	= 116 dB
4.	Distance Attenuation	= - 20 log (R / Ro)
	R = 150m between TBM and HKCC	= - 20 log (150 / 5.5)
		= - 29 dB
5.	Soil Damping	= 0 dB
	Through granite, assumed zero	
	Duilding Counting Land	- 10 dD
6.	Building Coupling Loss	= -10 dB
	at dominant frequencies between 63 Hz to 250 Hz	
	See Note [1]	
7.	Coupling Loss from	= -18 dB
	Bedrock to pile	
	(see attached calculation using SEA Ref. F)	
8.	Floor to floor attenuation	= -1 dB
	See Note [1]	for a conservative assessment
	Communication from Vibration to Naise	= - 27 dB
9.	Conversion from Vibration to Noise	21 db
	See Note [1]	
10.	Conversion to A-weighted Noise	= -20 dB
	Ref. FTA Guidance Manual Table 6-1	for a conservative assessment
11.	Predicted Groundborne Noise	= 11 dB(A)
	Adding items [3] to [10]	

Notes

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 22-Dec-03

NSR: Typical Schools along Canton Road

Item	Description	Quantity
1.	Source Term, from Graph	= 2.5 mm/s
	DB320 Kwai Tsing Tunnel by Extrapolation	
	PPV at 5.5m	
2.	Conversion to rms velocity	= 0.625 mm/s
	based on Crest factor of 4	
	Reference: FTA Guidance Manual	
3.	Vibration Velocity	= 20 log (V / Vref)
	ref. 10^-9 m/s	= 116 dB
4.	Distance Attenuation	= - 20 log (R / Ro)
	R = 5m between TBM and NSR	= - 20 log (5 / 5.5)
		= 0 dB
5.	Soil Damping	= 0 dB
	Through granite, assumed zero	
6.	Building Coupling Loss	= -10 dB
	at dominant frequencies	
	between 63 Hz to 250 Hz	
	See Note [1]	
	Counties I are from	= 40 dD
7.	Coupling Loss from	= -18 dB
	Bedrock to pile (see attached calculation using SEA Ref. F)	
	(See attached calculation using SEA Ref. F)	
8.	Floor to floor attenuation	= -2 dB
<u> </u>	See Note [1]	-1 dB per floor for a conservative assessment
	loce Hote [1]	T do per neer to a conservative assessment
9.	Conversion from Vibration to Noise	= - 23 dB
	See Note [1]	
10.	Conversion to A-weighted Noise	= -20 dB
*	Ref. FTA Guidance Manual Table 6-1	for a conservative assessment
11.	Predicted Groundborne Noise	= 43 dB(A)
	Adding items [3] to [10]	
		

Notes

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 11-Dec-03

NSR: Typical Hotel Rooms along Canton Road

Item	Description	Quantity
1.	Source Term, from Graph	= 2.5 mm/s
	DB320 Kwai Tsing Tunnel by Extrapolation	
	PPV at 5.5m	
2.	Conversion to rms velocity	= 0.625 mm/s
	based on Crest factor of 4	
	Reference: FTA Guidance Manual	
3.	Vibration Velocity	= 20 log (V / Vref)
	ref. 10^-9 m/s	= 116 dB
4.	Distance Attenuation	= - 20 log (R / Ro)
	R = 10m between TBM and NSR	= - 20 log (10 / 5.5)
		= - 5 dB
5.	Soil Damping	= 0 dB
	Through granite, assumed zero	
6.	Building Coupling Loss	= -10 dB
······································	at dominant frequencies	
	between 63 Hz to 250 Hz	
	See Note [1]	
7.	Coupling Loss from	= -18 dB
	Bedrock to pile	
	(see attached calculation using SEA Ref. F)	
8.	Floor to floor attenuation	= -3 dB
	See Note [1]	-1 dB per floor for a conservative assessment
9.	Conversion from Vibration to Noise	= - 27 dB
	See Note [1]	
10.	Conversion to A-weighted Noise	= -20 dB
	Ref. FTA Guidance Manual Table 6-1	for a conservative assessment
11.	Predicted Groundborne Noise	= 33 dB(A)
11,	Adding items [3] to [10]	00 00(1)
	Adding items [5] to [10]	

Notes:

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 11-Dec-03

NSR: Typical Residential units along Canton Road

Item	Description	Quantity
1.	Source Term, from Graph	= 2.5 mm/s
	DB320 Kwai Tsing Tunnel by Extrapolation	
	PPV at 5.5m	
2.	Conversion to rms velocity	= 0.625 mm/s
	based on Crest factor of 4	
	Reference: FTA Guidance Manual	
3.	Vibration Velocity	= 20 log (V / Vref)
	ref. 10^-9 m/s	= 116 dB
4.	Distance Attenuation	= - 20 log (R / Ro)
	R = 10m between TBM and NSR	= - 20 log (10 / 5.5)
		= - 5 dB
5.	Soil Damping	= 0 dB
	Through granite, assumed zero	
6.	Building Coupling Loss	= -10 dB
	at dominant frequencies	
	between 63 Hz to 250 Hz	
	See Note [1]	
7,	Coupling Loss from	= -18 dB
	Bedrock to pile	
	(see attached calculation using SEA Ref. F)	
	(coo attached carculation doing obstition t)	
8.	Floor to floor attenuation	= -3 dB
	See Note [1]	-1 dB per floor for a conservative assessment
9.	Conversion from Vibration to Noise	= - 27 dB
	See Note [1]	
10.	Conversion to A-weighted Noise	= -20 dB
	Ref. FTA Guidance Manual Table 6-1	for a conservative assessment
11.	Predicted Groundborne Noise	= 33 dB(A)
- * * * * * * * * * * * * * * * * * * *	Adding items [3] to [10]	
	g and the first	

Notes:

APPENDIX - 7-2-4

Sample Construction Groundborne Noise Calculations for Pipepile

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 5-Jan-04

NSR: HKCC Studio Theatre

Item	Description	Quantity
1.	Calculated 4 nos. Hydraulic Breakers	= 30 dB(A)
	Noise Level at HKCC Studio Theatre	Extracted from calculation sheet Ref. D3
	when breaking granite at 22m away	
2.	Calculated 1 nos. Hydraulic Breakers	= 30 dB(A) minus 6 dB(A)
	Noise Level at HKCC Studio Theatre	= 24 dB(A)
	when breaking granite at 22m away	
3.	Correction to Pipepile Noise	= + 20 log (V1 / V2)
	V1 = Vibration (rms) of Pipepile	= + 20 log (0.638 mm/s / 0.298 mm/s)
	V2 = Vibration (rms) of Hydraulic Breaker	= + 6.6 dB
	Ref.	
	See vibration measurement table Appendix 7-1	
5.	Predicted Groundborne Noise	= 31 dB(A)
	Adding items [2] and [3]	

Note:

[1] Pipepile vibration ppv at 2m = 19.3 mm/s, converted to rms using crest factor of 4 and distance 5.5m Pipepile Vibration (rms) at 5.5m = ppv/crest factor x (distance / reference distance)²

 $= (19.3/4)x(2/5.5)^2$

= 0.638 mm/s

Job No.: 23573

Project: KOWLOON SOUTHERN LINK KSL GSA-5100 EIA & ASSOCIATED SERVICES

Date: 5-Jan-04 NSR: YMCA Building

Item	Description	Quantity
1.	Calculated 4 nos. Hydraulic Breakers	= 37 dB(A)
	Noise Level at YMCA Building	Extracted from calculation sheet Ref. E3
	when breaking granite at 11m away	
2.	Calculated 1 nos. Hydraulic Breakers	= 37 dB(A) minus 6 dB(A)
	Noise Level at YMCA Building	= 31 dB(A)
	when breaking granite at 11m away	
3.	Correction to Pipepile Noise	= + 20 log (V1 / V2)
	V1 = Vibration (rms) of Pipepile	= + 20 log (0.638 mm/s / 0.298 mm/s)
	V2 = Vibration (rms) of Hydraulic Breaker	= + 6.6 dB
	Ref.	
	See vibration measurement table Appendix 7-1	
5.	Predicted Groundborne Noise	= 38 dB(A)
	Adding items [2] and [3]	

Note:

[1] Pipepile vibration ppv at 2m = 19.3 mm/s, converted to rms using crest factor of 4 and distance 5.5m Pipepile Vibration (rms) at 5.5m = ppv/crest factor x (distance / reference distance)² = $(19.3/4)x(2/5.5)^2$

= 0.638 mm/s