

**Proposed Temporary Open Storage and Warehouse for Storage of Construction Materials for a Period of 3 Years and Filling of Land at Lot 1302 RP (Part) in D.D. 118, Tai Shu Ha Road West, Yuen Long, New Territories**

---

**Annex 1 Drainage Proposal**

**1.1 Existing Situation**

**A. Site particulars**

- 1.1.1 The application site occupies an area of about 706m<sup>2</sup>.
- 1.1.2 The site is serviced by a vehicular access leading from Tai Shu Ha Road West. The area adjacent to the proposed development is mainly rural in nature.

**B. Level and gradient of the subject site & proposed surface channel**

- 1.1.3 It has a gradient sloping from southwest to northeast from about +22.0mPD to +21.8mPD. (**Figure 4**)

**C. Catchment area of the proposed drainage provision at the subject site**

- 1.1.4 The land to the north, west and east is found lower in level than the application site. The land to the south of the application site is found higher than the application site until it reaches a river which intercepts the stormwater from the higher land to the south. As such, an external catchment is identified in **Figure 5**.

**D. Particulars of the existing drainage facilities to accept the surface runoff collected at the application site**

- 1.1.5 As shown in **Figure 4**, a river is found to the northeast of the application site. The stormwater intercepted by the proposed surface channel at the application site will be dissipated to the said river.

## 1.2 Runoff Estimation

1.2.1 Rational method is adopted for estimating the designed run-off

$$Q = k \times i \times A / 3,600$$

Assuming that:

- i. The area of the catchment is approximately 3,500m<sup>2</sup>; (**Figure 4**)
- ii. Although the application site will be paved, the adjacent land within the external catchment are zoned for 'Agriculture' and all of them are unpaved. It is assumed that the value of run-off co-efficient (k) is taken as 0.9.

$$\text{Difference in Land Datum} = 23.6\text{m} - 21.8\text{m} = 1.8\text{m}$$

$$L = 93\text{m}$$

$$\therefore \text{Average fall} = 1.8\text{m in } 93\text{m} \text{ or } 1\text{m in } 51.67\text{m}$$

According to the Brandsby-Williams Equation adopted from the "Stormwater Drainage Manual – Planning, Design and Management" published by the Drainage Services Department (DSD),

$$\text{Time of Concentration (t}_c) = 0.14465 [ L / (H^{0.2} \times A^{0.1}) ]$$

$$t_c = 0.14465 [ 93 / 1.94^{0.2} \times 3,500^{0.1} ]$$

$$t_c = 5.21 \text{ minutes}$$

With reference to the Intensity-Duration-Frequency Curves provided in the abovementioned manual, the mean rainfall intensity (i) for 1 in 50 recurrent flooding period is found to be 275 mm/hr

***By Rational Method,***

$$Q_1 = 0.9 \times 275 \times 3,500 / 3,600$$

$$\therefore Q_1 = 240.63 \text{ l/s} = 14,437.5 \text{ l/min} = 0.24\text{m}^3/\text{s}$$

In accordance with the Chart or the Rapid Design of Channels in "Geotechnical Manual for Slopes", for an approximate gradient of about 1:100 in order to follow the gradient of the application site, 375mm surface U-channel along the site periphery is considered adequate to dissipate all the stormwater accrued by the application site and adjacent land.

### **1.3 Proposed Drainage Facilities**

- 1.3.1 Subject to the calculations in 1.2 above, it is determined that proposed 375mm concrete surface U-channel along the site periphery is adequate to intercept storm water passing through and generated at the application site (**Figure 4**).
- 1.3.2 The collected stormwater will then be discharged directly to the river to the northeast of the application site as shown in **Figure 4**.
- 1.3.3 All the proposed drainage facilities will be provided and maintained at the applicant's own expense. Also, sand trap and surface U-channel will be cleaned at regular interval to avoid the accumulation of rubbish/debris which would affect the dissipation of storm water.
- 1.3.4 The provision of the proposed surface channel will follow the gradient of the application site. All the proposed drainage facilities will be constructed and maintained at the expense of the applicant.
- 1.3.5 Prior to the commencement of the drainage works, the applicant will seek consent from District Lands Office/Yuen Long and relevant land owners for the provision of drainage facilities outside the application site.
- 1.3.6 The proposed development would not affect the existing ditches, drains and obstruct the flow of the flow of surface runoff.
- 1.3.7 The provision of surface channel at site boundary is detailed hereunder:
- (a) Soil excavation at site periphery, is inevitably for the provision of surface channel. The accumulation of excavated soil at the site periphery would obstruct the free flow of the surface runoff from the surroundings. Hence, the soil will be cleared at the soonest possible after the completion of the excavation process.
  - (b) In view of that soil excavation may be continued for several working days, surface channel will be dug in short sections and all soil excavated will be cleared before the excavation of another short section.
  - (c) 100mm gap will be provided at the toe of site hoarding to allow unobstructed flow of surface runoff.


## Annex 2 Estimated Traffic Generation

- 2.1 The application site is accessible via a vehicular track leading from Tai Shu Ha Road West. It is intended to serve the long term storage of mobile toilet at the site so that the traffic generated by the proposed development is insignificant.
- 2.2 The proposed parking space at the application site would only be opened to staff and no visitors is allowed to visit the proposed development.
- 2.3 There will be one loading/unloading bay for light goods vehicle not exceeding 5.5 tonnes. No medium/heavy goods vehicle and container trailer/tractor will access/park at the application site. The estimated traffic generation/attraction rate is shown below:

Type of Vehicle	<u>Average</u> Traffic Generation Rate (pcu/hr)	<u>Average</u> Traffic Attraction Rate (pcu/hr)	Traffic Generation Rate at <u>Peak Hours</u> (pcu/hr)	Traffic Attraction Rate at <u>Peak Hours</u> (pcu/hr)
Light goods vehicle	0.15	0.15	1.5	0

Note:

1. The operation hours of the proposed development is from 9:00a.m. to 7:00p.m. from Mondays to Saturdays. No operation will be carried out on Sundays and public holidays.
  2. The pcu of light goods vehicle is taken as 1.5; &
  3. Morning peak is defined as 7:00a.m. to 9:00a.m. whereas afternoon peak is defined as 5:00p.m. to 7:00p.m.
- 2.5 In association with the intended purpose, adequate space for manoeuvring would be provided within the application site. Sufficient space within the application site is provided so that no queueing up of vehicle would be occurred outside the application site.



**Application Site**


Project 項目名稱:  
 Proposed Temporary Open Storage and Warehouse for Storage of Construction Materials for a Period of 3 Years and Filling of Land at Lot 1302 RP (Part) in D.D. 118, Tai Shu Ha Road West, Yuen Long, New Territories

Drawing Title 圖目:  
**Site Plan**

Drawing No. 圖號:  
**Figure 1**

Remarks 備註:

Scale 比例:  
 1:1000



Project 項目名稱:

Proposed Temporary Open Storage and Warehouse for Storage of Construction Materials for a Period of 3 Years and Filling of Land at Lot 1302 RP (Part) in D.D. 118, Tai Shu Ha Road West, Yuen Long, New Territories

Drawing Title 圖目:

Proposed Layout Plan


Remarks 備註:

Drawing No. 圖號:

Figure 2

Scale 比例:

1:1000



Project 項目名稱:

Proposed Temporary Open Storage and Warehouse for Storage of Construction Materials for a Period of 3 Years and Filling of Land at Lot 1302 RP (Part) in D.D. 118, Tai Shu Ha Road West, Yuen Long, New Territories

Drawing Title 圖目:

Proposed Land Filling Plan

Drawing No. 圖號:

Figure 3


Remarks 備註:



Proposed Filling of 200mm thick concrete

Scale 比例:

1:1000



Project 項目名稱:

Proposed Temporary Open Storage and Warehouse for Storage of Construction Materials for a Period of 3 Years and Filling of Land at Lot 1302 RP (Part) in D.D. 118, Tai Shu Ha Road West, Yuen Long, New Territories

Drawing Title 圖目:

Proposed Drainage Plan

Drawing No. 圖號:

Figure 4

Remarks 備註:

- Proposed catchpit
- Flow of surface runoff
- + Level (in mPD)
- External catchment
- Catchpit with sand trap

Scale 比例:

1:1000